

REGULATIONS & REQUIREMENTS



112 OTTER AVE, PO BOX 2808 OSHKOSH, WI 54903-2808

> OSHKOSH (920) 232-3344 FOX CITIES (920) 727-2880 FAX (920) 232-3347

zoningdepartment@winnebagocountywi.gov

**LOCATION:** The following minimum setbacks apply to garages and sheds:


## Attached Garages:

- 30ft. from road right-of-way
- 25ft. from rear lot line
- 7ft, from one side lot line
- 10ft. from other side lot line
- 75ft, from water\*

## **Detached Garages/Sheds:**

- 30ft. from road right-of-way
- 3ft. from side lot lines
- 3ft, from rear lot lines
- 10ft. between detached structures
- 75ft, from water\*

**HEIGHT:** The height of an attached garage may not exceed a maximum height of 35 ft. The height of a detached garage/shed may not exceed a maximum height of 18 ft. Height is generally measured from grade to the mid-peak as shown in the right diagram. For additional diagrams, see Exhibit 8-3 in the Zoning Code.



**SIZE LIMITATIONS:** The maximum floor area allowed for accessory structures (attached and detached garages, sheds, gazebos, lean-tos, etc.) is determined by the zoning district and lot size of the parcel. No variances are allowed. A boathouse is not included in this limitation. Please contact Zoning Staff for the maximum floor area allowed for a specific property.

**YARD SHED:** One yard shed is allowed per lot without a zoning permit\*\* and without contributing to the maximum allowed accessory building floor area. The structure must be 100 sq. ft. or less and may not exceed a height of 8ft. The structure must still meet all required setbacks.

\*\*If in a shoreland area, a zoning permit may still be required for a yard shed.

## SPECIAL STANDARDS:

- A garage shall be of conventional wood-frame, metal-frame, or masonry construction. Softsided structures and canopies are specifically prohibited
- A garage or shed shall not be located in any easement.
- Additional impervious surface requirements may apply in the shoreland areas.
- Additional requirements apply if construction within the floodplain.

\*\*\*A zoning permit is required for the construction of a garage or shed.\*\*\*

<sup>\*</sup> The 75ft setback from water is measured from the closest point of the ordinary high water mark (OHWM) of a navigable water body. The Ordinary High Water Mark is delineated by zoning staff.