## S. 10 CONTROL OF EROSION AND POLLUTANTS DURING LAND DISTURBING CONSTRUCTION ACTIVITY

- (a) **GENERAL APPLICABILITY**. These general applicability provisions apply to the following land-disturbing construction activities, excluding that otherwise regulated by the DSPS under Wisconsin Admin. Code SPS 321.125.
- (b) Those involving grading, removal of protective ground cover or vegetation, excavation, land filling or other activity affecting a surface area of 4,000 square feet or more;
- (c) Those involving excavation or filling or a combination of excavation and filling affecting 400 cubic yards or more of soil, sand, or other excavation or fill material;
- (d) Those involving public or private access drives, street, highway, road, or bridge construction, enlargement, relocation or reconstruction longer than 125 feet;
- (e) Those involving the laying, repairing, replacing or enlarging of an underground pipe or facility for a continuous distance of 100 feet or more. The term pipe or facility includes, but is not limited to, utilities such as telephone, electric, gas, sanitary, storm water, etc.; NOTE: see S.11(5);
  - Those involving the construction or reconstruction of a continuous distance of 100 lineal feet of road ditch, non-agricultural grass waterway, or other non-agricultural land area where drainage occurs in an open channel; NOTE: see S.11(5)
- (f) Other land development activities, including access drives, that the administering authority determines have a significant impact.
- (g) Construction of any structure greater than 1000 square feet
- (h) Construction of any addition to a structure greater than 1000 square feet

Construction of multiple additions and/ or structures where the total area combined is greater than 1000 square feet.